





SCALE 5:1

300 S. DAYTON ST. DAVISON, MI 48423 PH: 810-653-9626 FAX:810-654-2616

Part Weight		T	
Min/Max Temp.	-30/140 Degrees F	.X=	
Pressure Tested	4.3 PSI		
Material	Flexible PVC		
Installation Torque	60" Lbs.	UNLESS	
Conforms to ASTM	D5926		
Box Quantity	40	INCH	
Clamps used	300 Series		
		3RD AN	

TOLERANCES: $X = Fractional \pm ... XX = \pm .02$ $... XXX = \pm .030$ $... XXX = \pm 0.5^{\circ}$ SS OTHERWISE SPECIFIED DESCRIPTION: Cap 1 1/2" Plastic Pipe

QC-101

NOTES:
- SOME HIDDEN LINES NOT SHOWN
-BREAK ALL SHARP CORNERS
-REPORT ALL CHANGES TO ENGINEERING

PROPRIETARY AND CONFIDENTIAL

THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF PERNICO, INC. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF FERNCO, INC. IS PROHIBITED.

UNITS: INCHES	SIZE	D. Bro	ıdy		scale not to scale
3RD ANGLE PR DO NOT SCALE		CHECKER:	DATE:	8/3/2007	SHEET 1 OF 1